

SHIMOGA DIVISION.

Dated 1st March 1923.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 1st April 1923, for restoring Kavadi Bylekere tank Registered No. 514, Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1924.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 140 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kavadi Bylekere tank Registered No. 514 of Sorab Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of Kavadi Bylekere tank Registered No. 514, Sorab Taluk.

No.	Items of work	Per	Quantity
I. Bund—			
1	Clearing jungle, removing trees with roots and scraping grass	Lump sum	100
2	Earthwork including watering and tamping, etc.	Rs.	
3	Turfing the slopes of bund	C. yd.	6,979
4	Providing and fixing grade stones with bed slabs including cutting figures, etc., complete.	Sq. yd.	8,120
5	Providing and fixing top width stones, etc., complete	No.	22
6	Settling stones including fixing, painting and cutting	"	22
7	Registered No. stone including figuring and painting	"	1
8	Bench mark stones do do	"	1
9	Grange stone 12 feet long, including bed slab, fixing, painting, cutting figures, etc.	"	2
			1
II. Sluice—			
1	Earthwork cutting open the bund and refilling the same including consolidation.	C. yds.	68
2	Earthwork excavating for foundation		
3	Concrete in surki mortar	"	8
4	Burnt brick in surki mortar	C. ft.	159
5	Burnt stone slabs dressed 6" thick	"	236
6	Plastering with surki mortar	S. ft.	95
7	Cutting orifice and plug hole	Sqrs.	2.5
8	Teakwood plugs, iron rod, etc., with lock and key	No.	3
9	Cast iron pipes 9" dia. including cartings, etc., and cement jointing	R. ft.	1
			45
III. Waste weir; natural 125 feet long—			
	Clearing draft channel	Lump sum	25
		Rs.	

Dated 1st March 1923.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 1st April 1923, for Improving Mugalihalli Mugalikatte tank, Regd. No. 781 of Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving Mugalihalli Mugalikatte tank, Regd. No. 781 of Channagiri Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of restoring Mugalihalli Mugalikatte Tank Registered No. 781, Channagiri Taluk :—

No.	Items of works	Per	Quantity
I. Bund at R. L. 55-00 and top-width 6 throughout—			
1	Clearing bushes and cutting trenches wherever necessary	L. S. Rs.	50
2	Earthwork to bund including watering tamping, and consolidation, etc., complete ..	C. yd.	10,894
3	Turfing front and rear slopes of bund	Sq. yd.	8,330
4	Providing and fixing grade stones with bed slabs including numbering painting ..	Each	19
5	etc., complete.		
	Do index stones do	"	19
6	Dato stone, chiseling, painting, cutting figures, etc., complete	"	1
7	Registered No. stone do	"	1
8	Benchmark stones do	"	2
9	Gauge stone 12 ft. high do	"	1
II. Constructing sluice No. 1 at R. L. 43-50.—			
1	Earthwork cutting open the existing bund and refilling the same with consolidation, ...	C. yd.	113
2	Earthwork excavating foundation	"	10
3	Filling in foundation with concrete	C. ft.	270
4	Burnt brick in surki mortar	"	192
5	Burnt stone slabs dressed	Sq. ft.	65
6	Plastering with surki mortar	Sqres.	3
7	Providing and fixing cast-iron pipe 9" dia. including cement pointing of joints and carriage to site, etc., complete.	R. ft.	45
8	Providing teakwood plug with wellcut shoulder and iron lifting spear	L. S. Rs.	25
9	Cutting orifice plug and guide holes	"	3
III. Constructing a sluice No. 2 at R. L. 49-00.—			
1	Earthwork	C. yd.	2
2	Filling in foundation with concrete	C. ft.	42
3	Burnt brick in surki mortar	"	80
4	Burnt stone slabs dressed 4" to 6" thick	Sq. ft.	11
5	Plastering with surki mortar	Sqres.	1
6	Providing and fixing cast iron-pipe 9" dia including cement pointing of joints and carriage to site, etc., complete.	R. ft.	27
IV. Masonry waste weir 100 ft. long at R. L. 50-00.—			
1	Earthwork	C. yd.	146
2	Clearing approach channel	L. S. Cyds.	170
2A	Surki concrete	C. ft.	234
3	Burnt brick in surki mortar	"	1,347
4	Burnt stone slabs dressed 4" to 6" thick	Sq. ft.	328
5	Plastering with surki mortar	Sqres.	9-25
6	Rough stone work new with jelly packing, etc., complete	C. yd.	100

Dated 1st March 1923.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 1st April 1923, for restoring Gondichatnahalli katte Tank, Registered No. 1062 of Shimoga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1924.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineers's Office at Shimoga between the hours of 11 to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money and be superscribed, "Tender for restoring Gondichatnahalikatte Tank, Registered No. 1062 of Shimoga Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate of Improving Gondichatnahali tank, Registered No. 1062,
Shimoga Taluk.

No.	Items of work	Unit	Quantity
	Bund R. L. 55-00—		
1	Clearing jungle..	L. S. Rs.	25
2	Earthwork to bund ..	Cyds.	11,183
3	Turfing front and rear slopes ..	Sqres.	1,374
4	Grade stones ..	Each.	30
5	Bench mark stones ..	Do	2
6	Tank register No. stone ..	Do	1
7	Date stone ..	Do	1
8	Gauge stone ..	Do	1
9	Cutting grips and filling bund ..	Do	1
	Sluice No. 1 R. L. 48-00, 24ft. long—	L. S. Rs.	20
1	Earthwork ..		
2	Brick in surki mortar ..	L. S. Rs.	10
3	Plastering in surki mortar ..	Cft.	93
4	Concrete in Surki mortar ..	Sqre.	50
5	Stone-ware pipe including lead ..	Cft.	128
6	Front orifice slab ..	Rft.	28
7	Plug ..	Each	1
	Sluice No. 2 of Masonry R. L. 44-50—	Each	1
1	Dismantling present work ..		
2	Earthwork ..	L. S. Rs.	15
3	Brick in surki mortar ..	Cyds.	180
4	Plastering in surki mortar ..	Cft.	792
5	Burnt stone slabs ordinary ..	Sqres.	3
6	Do dressed ..	Sft.	139
7	Plug with rod complete ..	Sft.	62
	Sluice No. 3 of stone-ware pipe R. L. 48-50, 30' long—	L. S. Rs.	8
1	Earthwork ..		
2	Concrete in surki mortar ..	Cyds.	14
3	Plastering with do ..	Cft.	158
4	Stone-ware pipe including lead ..	Sqre.	50
5	Front orifice slab ..	Rft.	34
6	Plug ..	Each	1
	Waste-weir left 35' long at R. L. 50-00—	Each	1
1	Earthwork ..		
2	Brick in mortar ..	L. S. Rs.	5
3	Built stone slabs ..	Cft.	178
4	Plastering with mortar ..	Sft.	75
5	Rough stone work ..	Sqre.	1-00
	Waste-weir 45 feet long, Right R. L. 50-00—	Cyds.	8
1	Earthwork ..		
2	Brick in mortar ..	L. S. Rs.	5
3	Burnt stone slabs ..	Cft.	203
4	Plastering in mortar ..	Sft.	90
5	Rough stone work ..	Sqre.	1-50
		Cyds.	8

A. TANDONI RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 13th March 1923.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 30th April 1923, for constructing a Slaughterhouse and